



Antrim County Road Commission

DIETER AMOS, Kewadin
KEVIN GIAR, Bellaire
GODFREY "PETE" HOOGERHYDE, Elmira
ALLEN MUSALL, Manager

July 14, 2026

REQUEST FOR MDOT PAVING

Sealed bids will be received until 1:00 PM, Monday, July 20, 2026, at which time they will be publicly opened and read. Bids shall be received at the office of the Antrim County Road Commission, PO Box 308, 319 E. Lincoln St, Mancelona, Michigan 49659-0308. Bids will be tabulated and a recommendation will be made to the Board of County Road Commissioners at their next regular meeting.

The Antrim County Road Commission (ACRC) requests bids for the following:

PLEASE SEE ATTACHED REQUEST: Slope of work, Project locations and project quantities are all on the attachment. This will be a lump sum price for all locations. Bid can be submitted on a letterhead.

Shoulder aggregate and gravel approaches to be placed by others.

All mix shall contain PG 58 -28 liquid asphalt and shall comply with the enclosed Antrim County Road Commission Special Provision for Acceptance of HMA Mixture on Non-Federal Aid Projects 01/16/23. All traffic control shall be in accordance with the current MMUTCD part 6.

All pay items shall be in accordance with 2020 MDOT Standard Specifications for Construction and as modified herein.

All work shall be completed ASAP. Most areas are ready to pave now

The successful bidder shall enter into a contract with and provided by the road commission.

Label bid "**MDOT PAVING**" plainly on the outside of a sealed envelope.

The Antrim County Road Commission reserves the right to accept or reject any or all bids, to waive any irregularity or defect in a bid, or to accept that bid which in the opinion of the Road Commission is in the best interest of the county.

Allen Musall
Manager

encl: Schedule of Items (Itemized Bid Sheet)
SP for Acceptance of HMA Mixture on Non-Federal Aid Projects 01/16/23

PROJECT INFORMATION
M-66, M-88, AND ELLSWORTH ROAD PAVEMENT REPAIRS

Page 1 of 2

SCOPE OF WORK

The proposed work includes saw cutting, pavement removal, milling four inches of road gravel, and placing four inches of *HMA 4EL*, to match existing HMA elevation on M-66, M-88, and Ellsworth Road as shown in plans.

PROJECT LOCATIONS

There are six locations. One location on M-66, four locations on M-88, and one location on Ellsworth Road. Descriptions of each location are listed below.

Location 1: On M-66 approximately 4,455-feet north of Old State Highway, in Jordan Township, Antrim County. This location includes saw cutting and pavement removal for a 5-feet by 28-feet area, and a pavement repair of 28-feet by 35-feet.

Location 2: On M-88 approximately 1,980-feet east of US-31, in Central Lake Township, Antrim County. This location includes a pavement repair of 17-feet by 188-feet.

Location 3: On M-88 approximately 5,935-feet east of US-31, in Central Lake Township, Antrim County. This location includes a pavement repair of 18-feet by 167-feet.

Location 4: On M-88 approximately 480-feet west of Ellsworth Road, in Central Lake Township, Antrim County. This location includes a pavement repair of 14-feet by 220-feet.

Location 5: On M-88 approximately 1,030-feet east of Ellsworth Road, in Central Lake Township, Antrim County. This location includes a pavement repair of 4.5-feet by 35-feet (Location 5A), and saw cutting and pavement removal for a 6-feet by 6-feet area, and a pavement repair of 6-feet by 6-feet (Location 5B).

Location 6: On Ellsworth Road approximately 2,450 feet north of Bennett Hill Road, in Banks and Central Lake Townships, Antrim County. This location includes a pavement repair of 13-feet by 22-feet.

PROJECT QUANTITIES

Quantities are provided for informational use only.

Work Items	Quantity	Unit
HMA, 4EL	263	Ton
Saw Cut	52	Ft
Pavt, Rem	20	Syd

PROJECT QUANTITIES BY LOCATION

Quantities are provided for informational use only.

LOCATION 1

Work Items	Quantity	Unit
HMA, 4EL	24	Ton
Saw Cut	28	Ft
Pavt, Rem	16	Syd

LOCATION 2

Work Items	Quantity	Unit
HMA, 4EL	78	Ton

LOCATION 3

Work Items	Quantity	Unit
HMA, 4EL	73	Ton

LOCATION 4

Work Items	Quantity	Unit
HMA, 4EL	75	Ton

LOCATION 5A

Work Items	Quantity	Unit
HMA, 4EL	4	Ton
Saw Cut	24	Ft
Pavt, Rem	4	Syd

LOCATION 5B

Work Items	Quantity	Unit
HMA, 4EL	1	Ton

LOCATION 6

Work Items	Quantity	Unit
HMA, 4EL	7	Ton